

MAST
1D7

Time off _____

Time on _____

Total time _____

- NOTE** Ask your supervisor/instructor whether or not to perform the next action before proceeding.

- NOTE** Be careful when bolting down the thermostat housing. Make sure the thermostat is still in its recessed groove. Failure to do so will result in a broken housing and damaged thermostat. If in doubt, ask your supervisor/instructor.

9. Once the thermostat is installed, return the drained antifreeze back into the system.
10. Follow the manufacturer's procedure to bleed any air from the cooling system.
11. Apply the vehicle's parking brake and secure the vehicle with wheel chocks to prevent the vehicle from rolling. Also, place the exhaust hose over the exhaust pipe(s).
12. Start the vehicle and check for any leaks or overheating. Immediately shut off the vehicle if a leak or overheating is found. Repair any leaks, or determine the reason for overheating if present.
13. Return the vehicle to its beginning condition and return any tools that you may have used to their proper locations.
14. Have your supervisor/instructor verify satisfactory completion of this procedure, any observations found, and any necessary action(s) recommended.

Performance Rating

CDX Tasksheet Number: C735

0

1

2

3

4

Supervisor/instructor signature _____ Date _____